

**SHIP PRODUCTION COMMITTEE  
FACILITIES AND ENVIRONMENTAL EFFECTS  
SURFACE PREPARATION AND COATINGS  
DESIGN/PRODUCTION INTEGRATION  
HUMAN RESOURCE INNOVATION  
MARINE INDUSTRY STANDARDS  
WELDING  
INDUSTRIAL ENGINEERING  
EDUCATION AND TRAINING**

**September 1985  
NSRP 0226**

# **THE NATIONAL SHIPBUILDING RESEARCH PROGRAM**

**1985 Ship Production Symposium  
Volume I**

**Paper No. 3:**

**Web Fabrication Line - Results of a  
Feasibility Study**

**U.S. DEPARTMENT OF THE NAVY  
CARDEROCK DIVISION,  
NAVAL SURFACE WARFARE CENTER**

Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE <b>SEP 1985</b>		2. REPORT TYPE <b>N/A</b>		3. DATES COVERED <b>-</b>	
4. TITLE AND SUBTITLE <b>The National Shipbuilding Research Program 1985 Ship Production Symposium Volum1 Paper No. 3: Web Fabrication Line - Results of a Feasibility Study</b>				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) <b>Naval Surface Warfare Center CD Code 2230-Design Integration Tools Building 192 Room 128 9500 MacArthur Bldg Bethesda, MD 20817-5700</b>				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT <b>Approved for public release, distribution unlimited</b>					
13. SUPPLEMENTARY NOTES					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT <b>SAR</b>	18. NUMBER OF PAGES <b>8</b>	19a. NAME OF RESPONSIBLE PERSON
a. REPORT <b>unclassified</b>	b. ABSTRACT <b>unclassified</b>	c. THIS PAGE <b>unclassified</b>			

## DISCLAIMER

These reports were prepared as an account of government-sponsored work. Neither the United States, nor the United States Navy, nor any person acting on behalf of the United States Navy (A) makes any warranty or representation, expressed or implied, with respect to the accuracy, completeness or usefulness of the information contained in this report/manual, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately owned rights; or (B) assumes any liabilities with respect to the use of or for damages resulting from the use of any information, apparatus, method, or process disclosed in the report. As used in the above, "Persons acting on behalf of the United States Navy" includes any employee, contractor, or subcontractor to the contractor of the United States Navy to the extent that such employee, contractor, or subcontractor to the contractor prepares, handles, or distributes, or provides access to any information pursuant to his employment or contract or subcontract to the contractor with the United States Navy. ANY POSSIBLE IMPLIED WARRANTIES OF MERCHANTABILITY AND/OR FITNESS FOR PURPOSE ARE SPECIFICALLY DISCLAIMED.

## WEB FABRICATION LINE

### - RESULTS OF A FEASIBILITY STUDY -

By

Michael Tomzig

Sales Application Engineer

Oxytechnik Systems Engineering

### ABSTRACT

In 1974 OXYTECHNIK designed a web fabrication system comprising equipment for mechanized handling and welding stiffeners to plates and a conveying system.' This first concept was the basis for a feasibility study to investigate the possibilities of highly mechanized respectively automatic fabrication of webs for building ships.

This paper will discuss this feasibility study: the history, requirements, result, description, special features, and conclusion.

1. **HISTORY**

**In 1974 OXYTECHNIK designed a web fabrication system comprising equipment for mechanized handling and welding stiffeners to plates and a conveying system. This first concept was the basis for a feasibility study to investigate the possibilities of highly mechanized respectively automatic fabrication of webs for building ships.**

2. **REQUIREMENTS**

<b>Conception:</b>	<b>Manufacturing of webs consisting of pre-cut plates and pre-processed stiffeners, conveying system connecting different Stations.</b>
<b>Automation:</b>	<b>All major processes to be automated respectively highly mechanized as far as economical.</b>
<b>Dimensions of workpieces:</b>	<b>The line capable of handling webs and frames up to 54' length. max. plate width 13' thickness 5/16" to 1" stiffener length 1' to 13' stiffener height 18" stiffener type flat, T, L</b>
<b>Capacity:</b>	<b>Meeting the demands of AVONDALE Shipyards: 4 bulk carriers per year, 40.000 tons dead weight each.</b>
<b>Coating of plates and stiffeners:</b>	<b>Ability of handling coated materials respectively consideration of this influence on the welding speed, etc.</b>

3. **RESULT**

- Flow production on two lanes with integrated processing stations including all activities necessary for a stand alone condition,  
  
two lanes for transport of webs and web frames,
- main station designed as robot for handling, positioning, and welding of stiffeners to the plate oriented in all directions as required,
- Maintaining exact location of plates after marking and cutting until transport to the welding station.  
Control of welding robot derived from data of plate marking and cutting process.

4. **DESCRIPTION**

(see 'layout no. 734.07351 A)

**Station I**

The pallets consisting of two carriages will be connected and prepared for loading of plates.

**Station II**

The pallets will be loaded and positioned by crane, marked and labeled. Also bevel cuts are performed here, if required. All information will be transferred to the machine control from the main frame.

**Station III**

The pallets will be moved automatically to station III for simultaneous cutting on both lanes. All cut parts remain in their original location by leaving tabs.

#### Station IV

Joining of plates by welding tractors, if required.

#### Station V

Stiffeners will be removed automatically from a storage magazine attached to the machine, positioned at the correct location on the plate, pressed to the plate, and welded on both sides simultaneously. This robot is able to handle stiffeners of 3' to 12' length. Tacking is avoided.

#### Station VI

Stiffeners shorter than 3' are handled with a manually controlled positioner. Tacking and welding is done manually.

#### Station VII and VIII

Unloading and return of pallets.

In case of frames the pallets serve as support table for arranging, tacking, and welding face plates. To simplify this work face plate machines are provided, which hold the workpieces in the correct position before manual tacking and welding.

#### Station IX

Turning over by crane, line heating, adding further stiffeners, welding of bottom sides of face plate and butt joints.

### 5. SPECIAL FEATURES

- The transporting system can be adapted to several purposes. The normal use is for production of webs and frames as described. By joining pallets sidewise also panels up to 27' x 59' can be processed.

- All machines are arranged on same rails.
- Any handling of single cut plates is avoided reducing labour costs and production time.
- Cutting and marking information is utilized to control the robot.
- All mechanized stations require 7 operators. Manual work like turning over of plates, finishing of longitudinal welds, tacking, and welding of small stiffeners, etc. were not calculated.
- The capacity of the line can be increased by water plasma cutting.
- A material management and shop scheduling system may be developed to ensure a proper connection to the existent beam line, an optimum load, and a reliable availability of parts.

## **7. CONCLUSION**

**The feasibility study is a proposal based on specific requirements. Modifications easily can be made for individual needs. The robot as the heart of the line also can be used separately as a single station if a stand alone system including plate processing cannot be realized.**



Additional copies of this report can be obtained from the  
National Shipbuilding Research and Documentation Center:

**<http://www.nsnet.com/docctr/>**

Documentation Center  
The University of Michigan  
Transportation Research Institute  
Marine Systems Division  
2901 Baxter Road  
Ann Arbor, MI 48109-2150

Phone: 734-763-2465  
Fax: 734-936-1081  
E-mail: [Doc.Center@umich.edu](mailto:Doc.Center@umich.edu)